

***De-icer Installation at Lévis Substation on  
Hydro Québec's High Voltage System***

***Presenters***


***Chris Horwill : AREVA T&D***

***Hubert Bilodeau : Hydro Québec***

**IEEE T&D Conference, Chicago 2008**

***Background***

## Why a de-icer?




► In December 1998, the Québec region of Canada was hit by one of the worst ice-storms in recorded history

- The ice storm generated ice build-up as much as 75mm
- An accumulation of ice toppled hydro towers and downed hundreds of kilometres of high-voltage transmission lines.



## De-icer: Location




Line	Destination	Length	Voltage
7010	Laurentides	27km	735 kV
7010 +7020	Jacques Cartier	62km	735 kV
7097	Appalaches	78km	735 kV
7007	Bergeronnes	242km	735 kV
3078 / 3079	Rivière du Loup	183km	315 kV

### ► Main Ratings:

- ◆ Standard de-icer mode - "Nameplate rating" :
  - 250MW, 7200A /  $\pm 17.4$ kV @ +10°C
- ◆ Verification mode :
  - 200MW, 5760A /  $\pm 17.4$ kV @ +30°C
- ◆ 1 hour overload :
  - 300MW, 7200A /  $\pm 20.8$ kV @ +10°C
- ◆ Low ambient overload :
  - 275MW, 7920A /  $\pm 17.4$ kV @ - 5°C

## De-icer Mode: Main design ratings




- Because of the different characteristics of the sections, the operating range of current and voltage is large



## SVC Mode: Main design ratings

- Main ratings
  - ◆ Dynamic range
    - +225 Mvar / -115 Mvar at nominal voltage
  - ◆ Target voltage
    - 315 kV  $\pm$  5%
  - ◆ Slope
    - 3% on 225 Mvar

# Solution

# One line diagram





## *Studies*

## *Studies*

### ▶ Main scheme parameters

#### ◆ Design for both modes

- Use of AC coupling reactors for both modes
- Different temperature ranges for different modes
  - Affects the transformer and capacitors
- Different reactive power requirements for different modes

▶ **Filter performance and rating**

- ◆ **AC filter design for all modes**
  - Different harmonic generation from converters for different modes
  - Different temperature ranges for different modes
  - 13 different line connection arrangements in de-icer mode
- ◆ **DC filter design for de-icer and verification modes**
  - 13 different line connection arrangements in de-icer mode
  - 60Hz induction from parallel AC lines in de-icer mode

▶ **Transient studies**

- ◆ **Transient component ratings**
- ◆ **Surge arrester ratings**
- ◆ **Circuit breaker TRV**
- ◆ **Accidental imposition of 735kV or 315kV onto DC bus**



▶ **Insulation co-ordination**

- ◆ **Determination of clearances and creepages**
- ◆ **Enhanced insulation specified for insulators subject to ice**

▶ **Dynamic performance studies**

- ◆ **Step response in SVC mode**
- ◆ **Static characteristic**
  - **Characteristic defined at 315kV, but voltage measured at 735kV**
- ◆ **Overtoltage and undervoltage response**
- ◆ **Control loop stability in de-icer mode**
- ◆ **TSC switching in de-icer mode**

## *Control Performance Verification*

## *Testing of Control System*

- ▶ **Development of Master Control - DCU (De-icer Control Unit)**
- ▶ **Validation of DNP3 Communication**
- ▶ **Type test on *Real Control* (System V)**
- ▶ **Static and Dynamic Performance Test on *Development Control Cubicle* & Simulator**
- ▶ **Additional tests on a *Control Replica* at IREQ**

**Real Control (SVC/De-icer and VBE)**  
**subjected to a complete type tests program:**

### Immunity to Electrical Interference (EMC)

#### Primary Objectives

- No deviation of operating point beyond accuracy limits
- State of all digital I/O shall remain unchanged
- No lane changeover
- No report of a fault event by control system devices

### Environmental Tests

#### Primary Objectives

- No drifting of control operating point or total controls failure permissible due to thermal stress or humidity effects

**Performed on a Development Control Cubicle connected to Manufacturer's RTDS**

- ▶ TCR/De-icer and TSC firing pulses;
- ▶ Same application code;
- ▶ 2 lanes
- ▶ Additional H/W and software to simulate the plant inputs as required;
- ▶ Simulation of profibus outstation for switchgear monitoring.

### Development Control Cubicle and RTDS

#### Static Tests

- ◆ Sequence Control with DCU
- ◆ De-Icer Control
  - Control loops
  - De-icer Characteristic ( Voltage, Power and Line resistance)
  - Lane Changeover
- ◆ SVC Control
  - VI Curve in Voltage Control and Reactive Power Control
  - Open-loop Control
  - Lane Changeover
  - Special control function ( Gain Supervisor, Current limiter etc.)
- ◆ Harmonic Performance
- ◆ Valve Data Back
- ◆ Control System Internal faults
- ◆ AC Protection
- ◆ DC Protection

### Development Control Cubicle and RTDS


#### Dynamic Performance Tests


- ◆ SVC Mode: Small and large Disturbance step response
- ◆ De-Icer Mode: Step Response at High and Low Current
- ◆ Faults in De-icer mode
- ◆ 1-phase Bi-phase and 3 phase faults in SVC mode
- ◆ Response to frequency variation in SVC mode
- ◆ Stability Margin

### Replica connected to HYPERSIM (IREQ simulator)

### Primary Objectives

- ▶ **Provide additional testing facility** ( In parallel to Factory Test)
  - ◆ MBPSS( Multi-Band Power System Stabilizer)
  - ◆ Geomagnetic influence
  - ◆ Contingencies (additional validation)
- ▶ **Final validation of UCD**
- ▶ **Validation of Acceptance Test program**
- ▶ **Training (Operator and Field technician)**





UCD



HYPERMIM



RSPC1



### SYSTÈME DE DÉGLAÇAGE

**Commandes / Status**

- Retour à l'arrêt
- Retour à l'arrêt
- Prêt à débrancher
- Mise sous tension
- Mode Automatique
- Maintenance

**Température extérieure**

< 10°C | 10-19°C | 20-30°C | 30°C et +

**Indication**

- Configuration Déglaceur ouverte
- Déglaceur En Service
- Déglaceur En Attente
- Déglaceur Hors Tension
- Part 1 bloqué
- Part 2 bloqué
- TSC bloqué
- Ready en cours
- 7200
- Prêt à reprendre

**Reprendre**

**Liens et agencements**

Liens + zone	TOP	TOP	TOP	TOP + TOP
0 A/C	0 B/C	0 C/D	0 D/E	0 E/F
0 F/G	0 G/H	0 H/I	0 I/J	0 J/K

**Modes**

- Verification
- Prêt à partir

**Paramètres**

Unité	Defaut	Min	Max	Normal	Actuel	Etat	Message
Courant nominal	ACC	900					
Courant réglage	ACC	7000	800	7000	7000	VALEUR	7300
Courant maximum	ACC	7800	8800	7800	7815	VALEUR	
Tension	Min						315.0
Tension maximum	Min	41.7	34.8	42.5	47.7	VALEUR	
Resist. ligne Min	Ohms	5.28	5.28	14.93	5.28	VALEUR	5.28
Resist. ligne Max	Ohms	4.86	5.80	14.80	4.86	VALEUR	
Nombre armoires	Etages	0	0	0	0	VALEUR	0
Temps dégl.	Minutes	90	1	115	90	VALEUR	
Temps dégl. max	Minutes					VALEUR	0.1
Temps de rep. puissance	Secondes	525	5.81	1.80	5.25	VALEUR	
Temps de rep. initial	Sec	90	85	158	80	VALEUR	
Temps de rep. incr	Sec	50	3	65	50	VALEUR	

**Commandes / Status (Mode déglaceur)**

- Seq. en cours
- Seq. en attente
- Seq. complète
- Seq. bloquée (busy)
- Seq. arrêtée

Message: **CONTINUITÉ VALIDÉE. EN ATTENTE D'ACTION OPÉRATEUR**

Buttons: Exécuter, Conditionner manuellement, Suspendre, Arrêter

**Indications de sécurité**

- Line selected - Line 1
- Line selected - Line 2


Version du schéma: 20090902

## Preparation for the commissioning


### Deicer mode - particular tests singled out

1. Open Circuit Test Mode; intended for first time energization
2. Converter Deblocking in current control
3. Review trip sequence – Overvoltage caused by remote isolation of the converter
4. Dc voltage measurement failure
5. Ac Voltage Error (Fuse failure)


## Remote Isolation of the Converter



## Normal Shutdown Sequence by local breaker opening



## Deicer mode – Remote Shutdown




No control action  
Severe Overvoltage  
when connected to  
longest (247km) line



## Deicer mode – Remote Shutdown

### Preliminary investigation


Local detection preferred



Current detection &  
Control action

No Overvoltage

## Limitation of Overvoltage New Protection Philosophy



## *De-icer installation*

## *De-icer installation*

DC converter valves



AC coupling reactors



HV connections and transformer



Harmonic filters




DC filters and DC bus



# Commissioning

## TCR current

Mise en service du déglaceur - Poste Lévis  
Réduction par paliers du courant ICT  
Procédé 1.4 - Section 3.1 - Étape 39  
Jeudi 15 novembre 2007 - 19:15:23.681



▶ **Thank you for your attention**